



**Addendum No. 2  
Erie International Airport  
Rehabilitate and Expand Terminal Apron**

Rehabilitate and Expand Terminal

Project name: <u>Apron</u>	Client: <u>Erie Regional Airport Authority</u>
Project location: <u>Erie, PA</u>	Client representative: <u>Kimberlie Sharrer</u>
Project number: <u>3225600-201146.01</u>	Mead & Hunt, Inc. manager: <u>Sean Thompson</u>
Date: <u>March 5, 2021</u>	Mead & Hunt Inc. phone: <u>517.908.3103</u>

TO ALL BIDDERS: You are requested to make all changes and/or additions contained in this Addendum to the Bidding Documents. Failure to acknowledge this Addendum in Proposal may result in rejection of bid.

I. GENERAL

None

II. GENERAL QUESTIONS AND ANSWERS

None

III. PROPOSAL DOCUMENTS

- A. Bid Form to be replaced in its entirety with Bid Form enclosed in Addendum No. 2. This was missing from Addendum 1

IV. DRAWINGS

A. None

V. SPECIFICATIONS

A. None

END OF ADDENDUM

## PRICE FORM

**Failure to complete this form and submit by the Bid Deadline shall result in your Bid being deemed nonresponsive and rejected without any further evaluation.**

**The Airport Authority reserves the right to change the Estimated Quantities and their respective Item Sub-total and Total Price based on requirements of the Project. The successful Bidder (Contractor) will be paid for quantities installed in accordance with the Basis of Payment section of the Specifications. Unit Prices provided on this Price Form will be the prices used for any quantity additions and deductions required. The Bidder must complete the Price Form either by hand writing in ink or typing prices in the spaces provided. Bidders must provide a Unit Price for all items.**

### Bid Items

SPEC. NO.	ITEM NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM SUBTOTAL
C-100	100001	Contractor Quality Control Program (CQCP)	LS	1		
C-102	102001	Installation, Maintenance, and Removal of Erosion Control Measures	LS	1		
C-105	105001	Mobilization, 10% Maximum	LS	1		
C-105	105002	Safety and Security	LS	1		
C-105	105003	Permits	DLR	20,000		
P-101	101001	Pavement Removal, Asphalt	SYD	7,400		
P-101	101002	Pavement Removal, Concrete	SYD	3,600		
P-101	101003	Remove Drainage Structure	EA	8		
P-101	101004	Remove Storm Sewer	LFT	1,350		
P-101	101005	Remove Pavement Marking	SFT	9,000		
P-101	101006	Remove Electrical Manhole	EA	3		
P-101	101007	Deconstruct Electrical Manhole	EA	1		
P-101	101008	Remove Inset Edge Light and Base	EA	1		
P-101	101009	Remove Elevated Edge Light and Base	EA	39		
P-101	101010	Remove Elevated Edge Light, Base to Remain	EA	8		
P-101	101011	Remove Guidance Sign and Base	EA	9		
P-101	101012	Remove Electrical Duct Bank	LFT	1,500		
P-152	152001	Unclassified Excavation	CYD	19,656		
P-152	152002	Subgrade Undercut	CYD	2,000		
P-152	152003	<b>Select Borrow - AASHTO No. 1 Stone</b>	CYD	500		
P-154	154001	Subbase Course	CYD	5,850		
P-154	154002	Separation Geotextile	SYD	14,800		
P-209	209001	Crushed Aggregate Base Course	CYD	2,500		
P-401	401001	Asphalt Surface Course, Gradation 2	TON	450		
P-403	403001	Asphalt Mixture Base Course, Gradation 1	TON	2,750		
P-403	403002	Asphalt Mixture Base Course, Gradation 2	TON	1,900		
P-501	501001	Concrete Pavement, 12"	SYD	12,600		
P-603	603001	Emulsified Asphalt Tack Coat	GAL	1,300		
P-620	620001	Surface Preparation	LS	1		
P-620	620002	Airport Pavement Marking, Solid, Yellow, 1/2 Rate	SFT	3,600		
P-620	620003	Airport Pavement Marking, Solid, Black	SFT	8,500		
P-620	620004	Airport Pavement Marking, Solid, White, with Reflective Beads	SFT	3,500		
P-620	620005	Airport Pavement Marking, Solid, Yellow, with Reflective Beads	SFT	3,600		
P-620	620006	Airport Pavement Marking, Solid, Red, with Reflective Beads	SFT	1,300		
P-620	620007	Temporary Airport Pavement Marking, Solid, Yellow, with Reflective Beads	SFT	1,000		
D-701	701001	12" Reinforced Concrete Pipe, Class V	LFT	1,956		

### Bid Items

SPEC. NO.	ITEM NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM SUBTOTAL
D-701	701002	18" Reinforced Concrete Pipe, Class V	LFT	136		
D-701	701003	<b>12" Reinforced Concrete Cylinder Pipe</b>	LFT	47		
D-701	701004	12" Corrugated Polyethylene Pipe	LFT	430		
D-701	701005	15" Corrugated Polyethylene Pipe	LFT	64		
D-701	701007	24" Corrugated Polyethylene Pipe	LFT	20		
D-701	701008	Detention Bed BMP-1	LS	1		
D-701	701009	Detention Bed BMP-2	LS	1		
D-751	751001	Inlet, Single Grate	EA	1		
D-751	751002	Inlet, Double Grate W/ Custom Box	EA	1		
D-751	751003	Inlet, Triple Grate	EA	1		
D-751	751004	Aircraft Rated Inlet, Single Grate	EA	1		
D-751	751005	Aircraft Rated Inlet, Single Grate W/ Type 10 Box	EA	1		
D-751	751006	Aircraft Rated Inlet, Single Grate W/ Custom Box	EA	1		
D-751	751007	Aircraft Rated Inlet, Triple Grate W/ Type 10 Box	EA	1		
D-751	751008	5' Diameter Manhole	EA	3		
D-751	751009	5' Diameter Manhole W/ Orfice Plate	EA	2		
D-751	751010	5' Diameter Aircraft Rated Manhole	EA	1		
T-901	901001	Seeding	AC	5		
T-908	908001	Mulching	SYD	24,200		
L-108	108001	No. 8 AWG, 5 KV, L-824, Type C Cable, Installed in Trench, Duct Bank or Conduit	LFT	12,000		
L-108	108002	No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed in Trench, Including	LFT	3,000		
L-108	108003	No. 1/0 AWG, Guard Wire, Installed in Trench, Including Connections/Terminations	LFT	800		
X-108	108004	24-Strand SM Fiber Optic Cable	LFT	1,500		
X-108	108005	36-Strand MM Fiber Optic Cable	LFT	1,200		
L-109	109001	Installation of Equipment with in Existing Vault or Prefabricated Metal Housing in Place	LS	1		
L-109	109002	Installation of Conduit and Equipment Connecting to Existing FAA Facility	LS	1		
L-110	110001	Directional Bore Electrical Conduit, 2-Way 4-Inch	LFT	600		
L-110	110002	Concrete Encased Electrical Duct Bank, 4-Way 3-Inch	LFT	200		
L-110	110003	Concrete Encased Electrical Duct Bank, 8-Way 3-Inch	LFT	400		
L-110	110004	Concrete Encased Electrical Duct Bank, 4-Way 4-Inch	LFT	500		
L-110	110005	Non-Encased Electrical Conduit, 1-Way 1 1/4-Inch	LFT	4,200		
X-110	110006	Polyethylene Innerduct, 1 Inch	LFT	3,700		
L-115	115001	Electrical Manhole, 4'x4'x4', Aircraft Rated	EA	2		
L-115	115002	Communication Manhole, 4'x4'x4', Aircraft Rated	EA	3		
L-125	125001	L-804(L) Elevated Runway Guard Light, Base Mounted, In Turf	EA	2		
L-125	125002	L-858 Relocated Guidance Sign, Base Mounted	EA	8		
L-125	125003	L-861 Incandescent Elevated Medium Intensity Runway Light, Base Mounted, In Turf	EA	1		
L-125	125004	L-861(L) Elevated Medium Intensity Taxiway Light, Base Mounted, In Turf	EA	24		
L-125	125005	L-861(L) Elevated Medium Intensity Taxiway Light, on Existing Base	EA	8		
L-125	125006	L-858 Guidance Sign Panel Replacement	LS	1		
L-125	125007	Electrical and Communication Investigation	LS	1		

### Bid Items

SPEC. NO.	ITEM NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM SUBTOTAL
-----------	----------	------------------	------	--------------------	------------	---------------

LIST ITEMS BELOW THIS LINE BY AMENDMENT


Bid Total Price = \$ \_\_\_\_\_  
(Amount in Numerals)

Bid Total Price = \$ \_\_\_\_\_  
(Amount in Written Words)

Bidder Signature: \_\_\_\_\_

Title: \_\_\_\_\_

Company: \_\_\_\_\_

Date: \_\_\_\_\_

Email: \_\_\_\_\_